



**New Albany, Indiana
Best Management Practices**

April 2006

TABLE OF CONTENTS

Preface (discussion / letter from MS4 jurisdiction)i

Acknowledgements (elected officials, MS4 Staff, and SWAC Members)ii

Table of Contentsiii

Section 1: Introduction..... 1-1

1.1 Background and Purpose 1-1

1.2 Stormwater Quality and Quantity Management..... 1-1

1.3 Construction Site Management for Stormwater Quality..... 1-2

1.3.1 Erosion Process..... 1-2

1.3.1.1 Water Erosion 1-2

1.3.1.2 Stream and Channel Erosion..... 1-3

1.3.1.3 Wind Erosion 1-3

1.3.1.4 Factors Influencing Erosion 1-3

1.3.2 Sedimentation Process..... 1-4

1.3.3 Other Stormwater Pollutants and Impacts 1-5

1.3.3.1 Nutrients 1-5

1.3.3.2 Oxygen Demanding Substances 1-5

1.3.3.3 Metals..... 1-5

1.3.3.4 Pesticides 1-5

1.3.3.5 Oil, Grease and Fuels..... 1-6

1.3.3.6 Other Toxic Chemicals 1-6

1.3.3.7 Miscellaneous Wastes 1-6

1.4 Post-Construction Management for Stormwater Quality 1-6

1.5 BMP Selection Process 1-7

1.5.1 BMP Objectives 1-7

1.5.2 BMP Categories..... 1-8

1.5.3 BMPs for Construction Site Management 1-10

1.5.3.1 Site Perimeter..... 1-12

1.5.3.2 Internal Swales and Ditches 1-13

1.5.3.3 Internal Erosion..... 1-13

1.5.3.4 Stormwater Inlets and Outfalls..... 1-14

1.5.4 BMPs for Good Housekeeping 1-14

1.5.5 BMPs for Post-Construction 1-15

Section 2: Construction Site Management Practices for Stormwater Quality 2-1

2.1 Site Planning and Design Practices – Fact Sheets

- SPD – 01 Protecting Sensitive Features
 - SPD – 01.1 Stream Corridors
 - SPD – 01.2 Wetlands
 - SPD – 01.3 Steep Slopes and Highly Erodible Lands
 - SPD – 01.4 Karst

- SPD – 02 Minimizing Impervious Surfaces
 - SPD – 02.1 Parking Lot Design
 - SPD – 02.2 Street Design
 - SPD – 02.3 Cul-de-sac Design
 - SPD – 02.4 Permeable Pavements
 - SPD – 02.5 Open-space Preservation
 - SPD – 02.6 Construction Phasing

- SPD – 03 Vegetative Practices
 - SPD – 03.1 Vegetative Buffers
 - SPD – 03.2 Disturbed Area Stabilization – Temporary Seeding
 - SPD – 03.3 Disturbed Area Stabilization – Permanent Seeding
 - SPD – 03.4 Disturbed Area Stabilization - Mulch
 - SPD – 03.5 Disturbed Area Stabilization - Sodding
 - SPD – 03.6 Erosion Control Mats/Blankets

- SPD – 04 Land Use Planning
 - SPD – 04.1 Covenants
 - SPD – 04.2 Setbacks and Buffers
 - SPD – 04.3 Conservation Easements

2.2 Erosion Prevention Practices - Fact Sheets

- EPP – 01 Tire Washing Facility
- EPP – 02 Construction Road Stabilization
- EPP – 03 Stabilized Construction Entrance
- EPP – 04 Buffer Zones
- EPP – 05 Temporary Seeding
- EPP – 06 Surface Roughening
- EPP – 07 Top Soiling
- EPP – 08 Mulching
- EPP – 09 Nets and Mats
- EPP – 10 Geotextiles
- EPP – 11 Terracing

2.3 Sediment Management Practices - Fact Sheets

- SMP – 01 Check Dams
- SMP – 02 Silt Fence
- SMP – 03 Straw Bale Barrier

- SMP – 04 Sand Bag Barrier
- SMP – 05 Brush or Rock Filters and Continuous Berms
- SMP – 06 Sediment Traps
- SMP – 07 Temporary Sediment / Detention Basin
- SMP – 08 Bank Stabilization
- SMP – 09 Rip-rap
- SMP – 10 Channel Linings
- SMP – 11 Temporary Diversions, Drains and Swales
- SMP – 12 Filter Strips
- SMP – 13 Temporary Inlet Protection
- SMP – 14 Temporary Outlet Protection

2.4 Good Housekeeping Practices - Fact Sheets

- GHP – 01 Dewatering Operations
- GHP – 02 Paving Operations
- GHP – 03 Structure Construction and Painting
- GHP – 04 Material Delivery, Storage, and Use
- GHP – 05 Spill Prevention and Control
- GHP – 06 Solid Waste Management
- GHP – 07 Hazardous Waste Management
- GHP – 08 Contaminated Soil Management
- GHP – 09 Concrete Waste Management
- GHP – 10 Sanitary/Septic Waste Management
- GHP – 11 Vehicle and Equipment Cleaning
- GHP – 12 Vehicle and Equipment Fueling
- GHP – 13 Vehicle and Equipment Maintenance
- GHP – 14 Employee/Subcontractor Training
- GHP – 15 Pesticides, Herbicides, and Fertilizer Use
- GHP – 16 Dust Control and Tracking
- GHP – 17 Maintenance of Collection Facilities and Appurtenances
- GHP – 18 Preservation and Maintenance of Existing Vegetation
- GHP – 19 System Flushing

Section 3: Post-Construction Pollution Prevention Practices 3-1

- 3.1 Stormwater Pollution Prevention - Fact Sheets
 - SPP – 01 Permanent Grass, Vines and Other Vegetation
 - SPP – 02 Geotextiles
 - SPP – 03 Buffer Zones
 - SPP – 04 Soil Bioengineering and Bank Stabilization
 - SPP – 05 Gradient Terraces and Slope Roughening
 - SPP – 06 Flow Diversions, Drains and Swales
 - SPP – 07 Outlet Protection
 - SPP – 08 Channel Linings

- 3.2 Stormwater Pollution Treatment Practices - Fact Sheets
 - STP – 01 Infiltration Systems
 - STP – 02 Wet Detention Ponds
 - STP – 03 Dry Detention Ponds
 - STP – 04 Constructed Wetlands
 - STP – 05 Biofilter, Swales and Strips
 - STP – 06 Media Filtration/Media Filters and Water Quality Inlets
 - STP – 07 Oil/Water Separators
 - STP – 08 Multiple Systems

Section 4: Additional Resources..... 4-1